

Longparish Infiltration Plan

Appendix B – Mitigation Measures



from
**Southern
Water** 

The Southern Water logo graphic consists of three stylized, wavy blue lines of varying lengths, positioned to the right of the text.

Appendix B

APPENDIX B

Mitigation measures

See notes in Section 4 regarding the potential need to introduce mitigation measures to reduce the risk of groundwater infiltration impacting the level of service provided by the sewerage system. Location of sites will be selected to provide the most effective arrangements to maintain services, whilst minimising environmental effects. Where practical, sites that have been used previously are expected to be re-used (when necessary), but the use of different locations cannot be ruled out, if hydraulic conditions dictate.

Tanker Locations



Longparish Layby – tankers will be deployed to the locations below (W3W:///resold.clerks.distracts)

Tankering occasionally occurs at this location from MH 0301.

Tankers will dispose at Fullerton WTW



Longparish Primary School – tankers will be deployed to the locations below (W3W///consented.gates.hatter)



Flows are occasionally managed via a private manhole just within the school gate.
Tankers will dispose at Fullerton WTW

